

Addendum/Corrigendum

A corrigendum/addendum is issued under the clause 17 of ITT as under.

Name of work: - Construction of EWS Housing, Club House, Convenient Shopping along with Development works like Internal Roads, Water Supply, Sewerage, Storm water drainage system, External Electrification and other Works contingent thereto at "Crestview" for Unitech Limited, Sector 70, Gurugram

Event Ref. No . - UL/KY/GRG/Crestview/2024/331

1. The Estimated cost is mentioned in Section-1, S.no (v) of NIT is Rs. 18.44 Crores, shall be read as **Rs. 19.11 Crs.**
2. The Estimated cost is mentioned in Annexure-1 General Details S.no (v) of NIT is Rs. 18.44 Crores, shall be read as **Rs. 19.11 Crs.**
3. The Estimated cost is mentioned in Section-2, S.no. 2 of ITT is Rs. 18.44 Crores, shall be read as **Rs. 19.11 Crs.**
4. The Schedule-B Non DSR amount mentioned in SOR page No.1 is Rs. 60807351, shall be read as **Rs. 67483838.**
5. The Schedule-B Non DSR amount mentioned in SOR page No.2 S.No A is Rs. 25347829, shall be read as **Rs. 32024316.**
6. The Schedule-B Non DSR amount mentioned in SOR page No.2 Subtotal is Rs. 60807351, shall be read as **Rs. 67483838.**
7. The Schedule-B Non DSR amount mentioned in SOR page No.62 is Rs. 60807351, shall be read as **Rs. 67483838.**
8. The Total amount is mentioned in SOR, page no.1 is Rs. 184436474, shall be read as **Rs. 191112961.**
9. The Total amount is mentioned in SOR, page no.2 is Rs. 184436474, shall be read as **Rs. 191112961.**
10. The Total amount is mentioned in SOR, page no.62 is Rs. 184436474, shall be read as **Rs. 191112961.**

The item mentioned in SOR at S.no 1.144, Item No. NSR, shall be read as under.

Sr.No.	DSR Code No. / NS Items	Item Description	Unit	Quantity	Rates in Rs	Amount in Rs	
						Schedule-A	Schedule-B
1.144	NSR	Construction of un-reinforced M-40 grade concrete pavement with dowel jointed, over a prepared sub base with 43 grade OPC cement @ 400 kg per cum coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a fully computerised batching and mixing plant as per approved mix design, transported to site in transit mixer with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing, complete as per clause 602 of MORT&H specifications. (Excess/less cement used as per design mix is payable/recoverable separately)	Cum	2518	9141		23017038

Note:- The EMD and tender document fee shall remain unchanged.